

INDIRA GANDHI INSTITUTE OF TECHNOLOGY: SARANG (PARJANG)

No. IGIT/EM/177

Date . 13.09.2022

QUOTATION CALL NOTICE

The Director, IGIT, Sarang invites sealed quotations from the registered supplier/contractor having valid PAN, GST and registration No for the following work/supply of materials. Quotations will be received on or before 26.09.2022 up to 03.00 P.M. and will be opened on 28.09.2022 at 10.00 A.M in presence of the quotationers.

Name of work:- Special Repair to Staff Quarters No-DR/08.

Sl.No.	Items	Unit	Quantity	Rate
1	Removing old lime or cement plaster from walls including racking out joints 16mm. Deep and removing the debries within 50m. Lead.	Sqm	14.0	
2	20mm thick grading plaster (1:4) including all cost and conveyance, royalty, taxes of all materials etc. complete as directed by the Engineer in Charge.	Sqm	6.0	
3	16mm thick plaster (1:4) including all cost and conveyance royalty taxes of all materials etc. complete as directed by the engineer in charge.	Sqm	8.0	
4	Providing & Fixing of Antiskid floor Tile on 20mm thick bed of cement mortar 1:4 (1 cement: 4 sand) jointed with neat cement slurry mixed with pigment to match the shades on the tiles etc. complete.	Sqm	3.68	
5	Providing & Fixing GLAZED tile in dado skirting and risers of steps on 12mm thick bed of cement mortar 1:3 (1 cement : 3 sand) jointed with neat cement slurry mixed with pigment to match the shades on the tile including rubbing and polishing complete including cost. of precast Tiles.	Sqm	14.0	
6	Distemping two coats on wall with distemper of approved shade of new work to give an even shade including cost of all materials and labour etc complete	Sqm	11.6	
7	Providing & Fixing of ACP Shutter including cost of all materials and labour etc complete.	Sqm	1.5	


P.H ITEM

1	P/F of Orissa Pan including all materials, transportation, labour etc. complete.	No	1	
2	P/F of PVC Cistern including all materials, transportation, labour etc. complete.	No	1	
3	P/F of CP Shower including all materials, transportation, labour etc. complete.	No	1	
4	15mm x 150mm long size CP shower arm including all materials, transportation, labour etc. complete.	No	1	

5	P/F of 20x600 mm CP Towel Rail including all materials, transportation, labour etc. complete.	No	1	
6	P/F of CP Angle valve including all materials, transportation, labour etc. complete.	No	1	
7	P/F of CP Bibcock including all materials, transportation, labour etc. complete.	No	1	
8	P/F of Concil Stopcock including all materials, transportation, labour etc. complete.	No	1	
9	Groove Cutting	Nos	10	
10	P/F 20 mm UPVC water Pipe including all materials, transportation, labour etc. complete.	Nos	15	
11	P/F of 110mm dia C.P grating including all materials, transportation, labour etc. complete.	No	1	
12	P/F 110 mm PVC Pipe including all materials, transportation, labour etc. complete.	Nos	10	
13	P/F of Soap dish including all materials, transportation, labour etc. complete.	No	1	
14	Hole Cutting	Nos	5	
15	P/F of 110 mm PVC Plain bend including all materials, transportation, labour etc. complete.	Nos	2	
16	P/F of Mirror including all materials, transportation, labour etc. complete.	No	1	

The authority reserves the right to reject any or all the quotations without assigning any reason Thereof.

Quotationers are requested to quote the rates including GST 12%.


13/09/2022
DIRECTOR

C.C. to:-- 1.Institute Notice Board.
2.Institute Web site.